



Hole Lengths - Approximate (in feet)				
Tee	Red		Blue	
Target	A	B	A	B
1	235		240	
2	175		200	
3	240		270	
4	235	274	283	322
5	229	295	310	376
6	251		321	
7	222		242	
8	240	307	255	322
9	260	275	372	395
10	240		300	

Hole Lengths - Approximate (in feet)				
Tee	Red		Blue	
Target	A	B	A	B
11	165			
12	270			
13				
14	255			
15	110+			
16				
17				
18				

Construction Notes:

- Tee areas can be at-grade or slightly (0.5") above grade.
- Finishing: texture desired on surface of pads - Dimpling with broom, or dragging across the short length (from long edge to long edge)
- Suggested that level ground be provided a minimum of 18" on both the left and right sides of tee pad and 36" in front and back of tee pad.
- Hole 5: Relocation of white signage on the left of fairway near wooden marquee. Suggest posting of "Caution - Disc Golf area, watch for flying discs" or similar signage as warning for multi-use patrons on both the tee area and approaching the target/basket area
- Hole 7: Red/blue (shared) tee pad requires large retention walls on right and left sides. Suggest posting of "Caution - Disc Golf area, watch for flying discs" or similar signage as warning for multi-use patrons as approaching the target/basket area from the large enclosed pavilion area.
- Hole 8: Red tee pad requires large retention walls on right and left sides. Blue tee pad at grade.
- Hole 10: Red and blue tee pads at grade. Suggest a landscaping tiered feature created to elevate target location due to standing water/drainage and also to create a signature look hole.
- Hole 10/11: Needs "Next Tee" signage to direct players to hole 11 tee areas.

CLEARING NOTES

- All trees for removal are painted with orange dot/square
- Relocate nature awareness signage on existing path to tee area on 15.
- Hole 11: Remove or fully trim all stubs from large palm 10 feet in front of tee area; Remove palms at 40'; Remove 4 or 5 tree and large pine at 120'; clear area 15' wider to left at target location
- Hole 12: Remove 2 pines early in fairway
- Hole 13: Remove large palm near tee; cut off broken/dead branch on oak mid-fairway; clear all small trees and brush to connect to main cleared area - clear from small path on left to large pine on right/center. In this area there is a large pine tree marked for removal but do not remove - paint says NO on tree.
- Hole 14: Clear back 20-30 feet behind tee area so we can increase length of hole. Remove palm at 100'. Remove tree at 180'. Remove low palms and dead trees just before target on right.
- Hole 15: Trim up tight or remove palm tree just behind tee. Remove two palms (low and high) at 70'. At current target, remove as much underbrush and palms to increase length of hole.
- Hole 16: Remove two trees 30' from tee on right near main opening to fairway from path.
- Hole 17: Clear entire hole - clear tee area backward through vines area, marked trees in main fairway, low palm under target area tree, clear out underbrush for 30-40' behind target.
- Hole 18: Clear entire hole - need swath cleared from tee to target which involves line trees and medium palms.

HOLE	TEE	TARGET	HOLE	TEE	TARGET
11	N27°06.349' W080°15.306'	N27°06.371' W080°15.321'	15	N27°06.481' W080°15.267'	N27°06.463' W080°15.259'
12	N27°06.382' W080°15.321'	N27°06.416' W080°15.307'	16	N27°06.446' W080°15.244'	N27°06.415' W080°15.243'
13	N27°06.426' W080°15.283'	N27°06.459' W080°15.270'	17	N27°06.399' W080°15.274'	N27°06.376' W080°15.247'
14	N27°06.462' W080°15.280'	N27°06.499' W080°15.271'	18	N27°06.373' W080°15.252'	N27°06.395' W080°15.282'



Notes:
 Signage - Each tee area will require a sign indicating hole length, par and flight path.
 - Additional signs for safety and directional signs for course flow also needed

Legend:

- Tee Box [Symbol]
- FCT Parcel [Symbol]
- Target [Symbol]
- Clearing/Grubbing [Symbol]
- Walking Path [Symbol]
- Waterway [Symbol]

Project Name:
 Halpatokee Park Disc Golf Course

Engineer of Record: Mark Janssen
 Version: 10.0
 Date: 7 September 2020

Janssen Productions
 1108 Lake Weldona Drive
 Orlando FL 32806